ENGINEERING DEPARTMENT.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 1st March 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 28th March 1933, for "Laying Street Sewers to be connected to Sub-main Sewer No. 2 passing along Balepet to Sultanpet, Bangalore City." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Sanitary Engineer's Office, between the hours of 11 A.M. to 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 2,000 in cash as earnest money, and be superscribed "Tender for Laying Street Sewers to be connected to Sub-main Sewer No. 2 passing along Balepet to Sultanpet, Bangalore City," in default of which, tenders will be rejected.

5. The final acceptance of the tender will rest with the Director of Health in Mysore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the Notice Board in the Executive Sanitary Engineer's Office, in due course. No enquries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for sitting out, barricading clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the Contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Sanitary Engineer after working out data with not more than 10 percent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Abstract estimate of quantities of work to be done.

	Particulars	Unit	Quantity
I.	Earthwork excavation for trenches for laying the pipe line including refilling trenches in layers of 1' watering and tamping to restore the surface to original ground level and forming sides, including cost of barricading and lighting and keeping watch for preventing accidents either by day or night, the contractor being responsible for any accident and restoring the surface of filled up trench in case of settlement. The excavation should be correct to levels and gradient given and in any case of extra depth excavated beyond this the Contractor will restore the surface to correct level by filling up with surki concrete at his own cost including shoring for the protection of sides of trench where necessary gravelly and ordinary soil.	Cyd.	9500
II.	Laying and jointing stoneware pipes with 1 to 1 cement mortar with necessary yarn caulking and finishing the joint including the cost of stoneware pipes of approved quality with perfect glaze and absolutely straight and without any flaw in the make and including all charges of testing the pipe line before the closing of the trench for pipes of sizes as in following :—	..	..
	7" Diameter	Rft.	15830
	(The pipe line will be kept open for the inspection of each joint by the Executive Sanitary Engineer or his representative and will not be closed without his permission.)	...	...

	Particulars	Unit	Quantity
III.	Constructing manholes of 4' diameter including earthwork excavation correct to the required dimension, cement concrete bed of 1 ft. depth and 6¾ ft. diameter, side walls of 1½ foet thick of brick in cement mortar 1 to 5, with necessary taper for fixing the manhole frame including the cost of cast iron heavy manhole cover and frame of 4 Cwt. and of design to be seen at the office and necessary number of cast iron steps of the standard design, making drains with cement concrete and cement plaster, ¾ of the depth of the pipe drain joining it and with 4" slope from side walls to drain and cement plastering ½" thick inside the manhole all over with 1 to 3 cement mortar, etc., complete of depths as in the following.—	...	...
	Up to 4 ft. depth	No.	30
	4 ft. to 5 ft depth	„	30
	5 ft. to 6 ft. depth	„	30
	6 ft. to 7 ft. death	„	25
IV.	Constructing flushing tank with masonry of capacity to contain 150 gallons of water and construction as per manholes including cost of flushing syphon of suitable size.	„	12
V.	Constructing ventilating shafts with 4" boiler tube of 16 ft. high masonry support including cement plastering to it and cost of cast iron bend and pipes up to manhole and fixing complete.	„	12
VI.	Carting surplus earth and clearing site and forming, etc., complete	Cyd.	2000
VII.	Providing and fixing 7" x 4" branches in the street sewers for connections.	No.	600
VIII.	Providing 4" S. W. pipe lines for house connections as in No. II and including earthwork complete.	Rft.	6000
IX.	Providing and fixing 4" stoneware trap including construction of cistern and fixing C. I. silt catcher budket as per design complete with rain water separating arrangements.	No.	600

B. R. GARUDACHAR,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, BANGALORE.

Abstract Notification dated 20th February 1933.

The attention of the public is invited to the notification calling for tenders for "Constructing a new Building for locating the Urdu Middle School at Hebbal, for Mysore State Troops, Bangalore, published on pages 223 to 224, of Part VI of the *Mysore Gazette*, dated 23rd February 1933. The last date for the receiving tenders is 10th March 1933.

N. NARASIMHA IYENGAR,
Assistant-Engineer.

BANGALORE BUILDINGS DIVISION, BANGALORE.

"Notification dated 1st March 1933."

Government having in their order No P. W. 1795–1811-3, dated 31st January 1933, sanctioned the conversion of the office of the Head Quarter Range, Bangalore in to "Buildings Division, Bangalore," all communications intended for the Range Office, will hereafter be addressed to the Executive Engineer, Bangalore Buildings Division, Bangalore.

A. TANDONI RAO,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification dated 20th February 1933.

Subject:—Constructing a girder bridge across the river Kabini at T.-Narasipur.

The attention of the public is drawn to notification calling for tenders for the above work in pages 215 to 223 of Part VI of the *Mysore Gazette*, dated 23rd February 1933.

K. NARAYANA IYENGAR,
Executive Engineer.

KADUR DIVISION.

Abstract Notification, Chikmagalur dated 15th February 1933.

The attention of the public is invited to the Notice calling for tenders for reconstructing the damaged bridge in 5—17th of Tarikere-Mangalore road published in detail on pages 204 to 205 in Part VI of the *Mysore Gazette*, dated 23rd February 1933. The last date for [illegible] tenders is 10th March 1933 till 3 P.M. Earnest money to be deposited is Rs. 60.

TUMKUR DIVISION.

Notification, dated 3rd March 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer Tumkur Division, up to 3 P.M., on 30th March 1933, for constructing a Primary School Building at Kallur in Gubbi Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of December 1933.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office, at Tumkur bettveen the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 175 in cash or currency notes as earnest money, and be superscribed "Tender for constructing a Primary School Building at Kallur in Gubbi Taluk" In default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Tumkur Division who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual bond, in default of which his tender will be cancelled, and earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates and measurements, quality of work, etc., and in all disputes of any kind the decision of the Executive Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lump sum provisions are subject to modification as per data worked out during the execution. For individual items of work under lump sum provisions the rates tendered for similar items of work will be paid and for other items the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

Abstract estimate for constructing a Primary School Building at Kallur in Gubbi Taluk.

Sl. No.	Items of work	Unit	Quantity	Rate in figures	Rate in words
				Rs.	Rs.
1	Earthwork excavating foundation and filling in basement.	C.yd.	47		
2	Stone jelly concrete in chunam mortar for foundation.	C.ft.	465		
3	Size stone in clay for foundation and basement including bond stones at 6' apart.	„	1.304		
4	Burnt brick in clay for superstructure	„	1.590		
5	Burnt brick in mortar	...	261		
6	Burnt stone slabs 6" thick roughly dressed and fixed.	S ft.	420		
7	Teak wood wrought and put up including wood oiling complete.	C.ft.	92·40		
8	Roofing with 1st class Mangalore tiles on teak reepers and wood oiling to reepers complete.	Sqr.	12·62		
9	Ridge tiles set in mortar and painted with cement.	R.ft.	79		

Sl. No.	Items of work	Unit	Quantity	Rate in figures	Rate in words
				Rs.	Rs.
10	Teak wood battened doors with iron clamps and fittings etc., complete.	S. ft.	39		
11	Teak wood windows with ½ panelled and ½ glazed or expanded metal and ¾" round iron bars clamps, fittings, etc., complete.	"	81		
12	Teak wood trellies work with fittings complete ...	"	9		
13	Pertorated brickwork including chunam and plastering complete.	"	41		
14	Flooring with burnt stone slabs 3" x 4" thick roughly dressed the joints and fixed on sand.	Sqr.	6·26		
15	Chunam plastering	"	36·95		
16	Whitewashing 2 coats	"	36·95		
17	Silicate painting 2 coats	"	2·49		
18	Chunam borders over gables roof 9" x 9" and plastering complete.	R.ft.	72		
19	Chunam painting to basement and cement washing.	Sqr.	3·00		
20	Zinc sheets for valleys 3" wide over the teak wood planks 3' wide and ½" thick including wood oiling and putting valley bunds in mortar and cement plastering complete.	R.ft.	56		
21	Teak wood cave boored plain 9" x 1" including chacolate painting and fixing complete.	"	178		
22	Clearing site and levelling ground and filling in basement if necessary.	Lump sum Rs.			
23	Sundry and unforeseen works such as showing false windows at rear end of rooms, putting black wall boards in cement mortar if necessary and providing glass tiles on roof.	Lump sum Rs.			
24	Pergola or pendal ... ... Burnt stone pillars 6" thick roughly dressed and fixed including cutting groves on top for pendal in front of the building.	... S.ft.	... 150		
25	Putting Longitudanal and cross bamboos including nails ropes and thatties or mats for covering, etc.	Lump sum Rs.			

N. G. KRISHNA IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

KOLAR DISTRICT.

Notification, dated 1st March 1933.

Notice is hereby given that the privilege of retail-vend of toddy in all the 31 shops of Bowringpet Taluk will be resold as a single unit for the unexpired portion of the triennial lease held by the present contractors from 1st July 1932 to 30th June 1935.

The resale will be conducted by the Deputy Commissioner on the 15th March 1933 at 2 P.M., in the Bowringpet Taluk Office.

The resale will be subject to the conditions laid down by Government in their Notification No. Fl. 5515—Ex. 78-29-2, dated the 17th February 1920 and amended in Government Notification No. Fl. 6587—Ex. 70-30-2, dated the 23rd February 1931 and Fl. 6638—Ex. 79-31-2, dated the 20th February 1932 and Excise Commissioner's Notification No. R. Dis. A1-645—31-32, dated the 7th March 1932.

The details of the 31 shops and consumption, etc., can be had from the District Excise Office, Kolar or in the Excise Range Office, Bowringpet.

T. G. RAMA IYER,